



UPC Positive Response Codes

Response Code	Response Description
Marked	
1A	Marked
1B	Marked: High profile utility in conflict.
1C	Marked: Permanent Marker Present.
1D	Marked: Ticket should have been white-lined but was not.
Marked with Exceptions	
2B	Marked with conditions: Privately owned facilities on property. Excavator needs to contact the private facility owner to determine how facilities will be located. If someone is needed to locate private utility lines, locators' listings may be found in the yellow pages under Utilities.
Unmarked	
3A	Unmarked: Locate technician could not gain access to complete the request. Locator will contact excavator.
3B	Unmarked: Incorrect address information; contact UPC to obtain a new ticket.
3C	Unmarked: Locate technician and contractor have agreed to meet on site on a specific date.
3H	Unmarked: Privately owned facilities on property. Excavator needs to contact the private facility owner to determine how facilities will be located. If someone is needed to locate private utility lines, locators' listings may be found in the yellow pages under Utilities.
3I	Unmarked: Marking instructions unclear. Locator will contact excavator.
3J	Unmarked: Extraordinary circumstances exist, contact the utility owner/operator directly for details.
3K	Unmarked: Not service provider for this location. Served by another provider.
3M	Unmarked: Late, Weather conditions - Contact utility owner/operator for further information.
3N	Unmarked: Late.
3Z	Unmarked: On-going job, locate technician and contractor have established a written agreement on scheduled marking.
Clear	
4A	Clear: No facilities
4B	Clear: 100% overhead facilities.
No Conflict	
5	No conflict, utility is outside of requested work site.
No Locate Required	
6	Excavator is contractor for facility owner. Locate required prior to excavation per contractual agreement.
Refuse to Locate	

UPC Positive Response Codes

7	Facility owner/operator refuses to locate. This is a violation of the statute.
Sewer Facilities	
8A	Sewer facilities and sewer laterals marked.
8B	Sewer facilities marked and sewer laterals marked with exception - Permanent Marker Present.
8C	Sewer facilities marked and sewer laterals marked as un-locatable with green triangle pointing to address or addresses in question
8D	Sewer facilities marked and sewer laterals unmarked: Sewer facility owner/operator has transmitted or mailed copy their best available sewer lateral records to the excavator.
8E	Sewer facilities marked and sewer laterals unmarked - This utility member is a local government that receives less than 50 requests per year. Please contact this sewer operator directly for further instructions concerning the sewer laterals.
8F	Sewer facilities have been marked and portions of sewer laterals present have been marked with or without exception and/or with green triangles. Portions are unmarked. Sewer facility owner operator will contact the excavator concerning unmarked portions in accordance with 8D or 8G.
8G	Sewer facilities marked and sewer laterals unmarked. Sewer facility owner/operator has scheduled an onsite meeting with the excavator.
Design Notifications	
9A	Design Locates: Marked.
9B	Design Locates: Marked with exceptions - Permanent Marker Present
9C	Design Locates: Unmarked: Contact Facility Owner/Operator for copy of drawings or other records.
9D	Design Locates: Clear, No Facilities.
Large Project Notifications	
10A	Large Projects: Meeting Date/Time Accepted.
10B	Large Projects: Meeting Date/Time Rejected.
10C	Large Projects: Agree to treat as a Large Project. Agreement signed.
10D	Large Projects: Disagree to treat as a Large Project - will mark in accordance with 25-9-6.
10E	Large Projects: Will not attend meeting - Not service provider for this location.
10F	Large Projects: Will not attend meeting - Clear, no facilities
10G	Large Projects: Not service provider for this location.
10H	Large Projects: Clear, no facilities
10I	Large Projects: Deviation to marking plan acknowledged and marked as requested.
10J	Large Projects: Deviation to marking plan acknowledged but not marked as requested. Locator will contact excavator.